



**Date:** June 22, 2017

**Addendum #:** 4

**Project Name:** Critical and Large Customer Improvements #1

**Bid Due Date:** Tuesday, June 27, 2017 at 10:00AM

Section 5A of the bid document has been revised as follows:

## 5. Material

A. The Owner will furnish most material required for the project. Not all material required for this project is listed.

i. <u>Owner-Furnished Material</u>	<u>Quantity</u>
1. Automatic Transfer Switch and Basement	1
2. 750 mcm cable	1,822'
3. 1/0 CU USE	2,000'
4. Terminations	15
5. 15kV Elbows	9
6. Recloser with Controller and Stand	1
7. Recloser with Stand	1
8. Solids Blade Disconnect Switch for New Recloser (Already Mounted)	6
9. Four Count Fiber Optic Cable	80'
10. Substation Arresters	3
11. Riser Pole Arresters	3
12. Animal Guard for New Recloser	6
ii. <u>Contractor Furnished Material</u>	
1. All Conduit and Sweeps	
2. Control Wire	
3. 500 mcm Bare CU	
4. Steel Riser (detailed drawing included on drawing #302 of Attachment A)	1
5. One Cable to Pad 0° (Suggested Part #SWL050B2, Hubbell)	6
6. One Cable to Pad 90° (Suggested Part #SWL050B2Y90, Hubbell)	3
7. T-tap for Arresters (Suggested Part #TCC8100025, Hubbell)	3
8. Any foreseeable item to complete construction in accordance with the drawings.	

Please see the following page for a grounding detail drawing for the Automatic Transfer Switch.

