



**Date:** March 28, 2018

**Addendum #:** 1

**Project Name:** Critical and Large Customers #2

**Bid Due Date:** Tuesday, April 3, 2018 at 2:00 PM

1. Owner-Furnished material is at a total cost of \$195,985.10.
2. Section 8. Directional Boring, Paragraph A indicates HDPE sweeps shall be supplied by the Contractor. Please note *all sweeps will be supplied by TCL&P.*
3. An updated staking sheet and material list is included with this addendum.



❖ MATERIAL LIST

Item	Qty	Description
UM6-1	18	200A Elbow
UM6-3	33	600A Elbow
UM6-10	21	200A Insulating Plug
UM6-11	3	600A Insulating Plug
UM6-13	24	600A -> 200A Reducing Plug
UM6-34	9	Elbow Arrestor
#750 MCM CU UG Pri	8700'	Okonite
#4/0 AL UG Pri	600'	Okonite
#4/0 CU	600'	Bare, annealed
Ground Rod	16	3/4" x 10', Copper Clad
Terminal Block	30	6 Position
PME Boxpad	1	
Pri Meter Boxpad	3	
600A Sec Cab Boxpad	3	
PME-10	1	S&C or Federal Pacific
Pri Meter	3	Durham APX
Seconalizing Cabinet	3	600A
6" Sweep	13	90° 60" Radius
6" Sweep	1	22.5° 60" Radius
6" Sweep	6	90° 48" Radius



❖ STAKING SHEET

Equip No.	Enclosure	Terminations/Elbows		Secondary			Ground	Misc.
		No.	Unit	No.	Conductor	Unit		
415	PME-10	3	UM6-3					EXISTIN G
		3	UM6-10					
		3	UM6-13					
32311	600A SEC CAB	6	UM6-3				UM48-6	UM1-5NC
32312	600A SEC CAB	6	UM6-3				UM48-6	UM1-5NC
32313	600A SEC CAB	6	UM6-3				UM48-6	UM1-5NC
		6	UM6-10					
		6	UM6-13					
419	PME-10	6	UM6-3				UM48-5	UM1-5NC
		6	UM6-10					
		6	UM6-13					
21	PRI METER	3	UM6-1				UM48-6	UM1-5NC
		6	UM6-3					
		3	UM6-10					
		3	UM6-11					
		9	UM6-13					
		3	UM6-34					
23	PRI METER	9	UM6-1				UM48-6	UM1-5NC
		3	UM6-34					
22	PRI METER	6	UM6-1				UM48-6	UM1-5NC
		3	UM6-10				UM48-6	UM1-5NC
		3	UM6-34				UM48-6	UM1-5NC